

# Q.PEAK DUO BLK ML-G10+ 385-405

ENDURING HIGH PERFORMANCE









## **BREAKING THE 20% EFFICIENCY BARRIER**

Q.ANTUM DUO Z Technology with zero gap cell layout boosts module efficiency up to 20.9%.



#### THE MOST THOROUGH TESTING PROGRAMME IN THE INDUSTRY

Q CELLS is the first solar module manufacturer to pass the most comprehensive quality programme in the industry: The new "Quality Controlled PV" of the independent certification institute TÜV Rheinland.



# **INNOVATIVE ALL-WEATHER TECHNOLOGY**

Optimal yields, whatever the weather with excellent low-light and temperature behavior.



#### **ENDURING HIGH PERFORMANCE**

Long-term yield security with Anti LID Technology, Anti PID Technology¹, Hot-Spot Protect and Traceable Quality Tra.Q™.



### **EXTREME WEATHER RATING**

High-tech aluminum alloy frame, certified for high snow (5400 Pa) and wind loads (4000 Pa).



#### A RELIABLE INVESTMENT


Inclusive 25-year product warranty and 25-year linear performance warranty<sup>2</sup>.

- $^{\rm 1}$  APT test conditions according to IEC / TS 62804-1:2015, method A (–1500 V, 96 h)
- $^{\rm 2}$  See data sheet on rear for further information.


# 6 BUSBAR CELL TECHNOLOGY

12 BUSBAR CELL TECHNOLOGY

#### THE IDEAL SOLUTION FOR:








#### **ELECTRICAL CHARACTERISTICS**

PO	WER CLASS			385	390	395	400	405
MIN	IIMUM PERFORMANCE AT STANDAR	D TEST CONDITIO	NS, STC1 (PO	WER TOLERANCE +	5W/-0W)			
	Power at MPP¹	P <sub>MPP</sub>	[W]	385	390	395	400	405
_	Short Circuit Current <sup>1</sup>	I <sub>sc</sub>	[A]	11.04	11.07	11.10	11.14	11.17
un u.	Open Circuit Voltage <sup>1</sup>	V <sub>oc</sub>	[V]	45.19	45.23	45.27	45.30	45.34
Minir	Current at MPP	I <sub>MPP</sub>	[A]	10.59	10.65	10.71	10.77	10.83
2	Voltage at MPP	V <sub>MPP</sub>	[V]	36.36	36.62	36.88	37.13	37.39
	Efficiency <sup>1</sup>	η	[%]	≥19.6	≥19.9	≥20.1	≥20.4	≥20.6
MIN	IIMUM PERFORMANCE AT NORMAL	OPERATING CONI	DITIONS, NM	OT <sup>2</sup>				
	Power at MPP	P <sub>MPP</sub>	[W]	288.8	292.6	296.3	300.1	303.8
Ξ	Short Circuit Current	I <sub>sc</sub>	[A]	8.90	8.92	8.95	8.97	9.00
ij	Open Circuit Voltage	V <sub>oc</sub>	[V]	42.62	42.65	42.69	42.72	42.76
₫	Current at MPP	I <sub>MPP</sub>	[A]	8.35	8.41	8.46	8.51	8.57
	Voltage at MPP	V <sub>MPP</sub>	[V]	34.59	34.81	35.03	35.25	35.46

¹Measurement tolerances P<sub>MPP</sub> ±3%; I<sub>SC</sub>; V<sub>OC</sub> ±5% at STC: 1000 W/m², 25±2°C, AM 1.5 according to IEC 60904-3 • ²800 W/m², NMOT, spectrum AM 1.5


#### Q CELLS PERFORMANCE WARRANTY



At least 98% of nominal power during first year. Thereafter max. 0.5% degradation per year. At least 93.5% of nominal power up to 10 years. At least 86% of nominal power up to 25 years.

All data within measurement tolerances. Full warranties in accordance with the warranty terms of the Q CELLS sales organisation of your respective country.

#### PERFORMANCE AT LOW IRRADIANCE



Typical module performance under low irradiance conditions in comparison to STC conditions (25 °C, 1000 W/m²)

TEMPERATURE COEFFICIENTS							
Temperature Coefficient of I <sub>SC</sub>	α	[%/K]	+0.04	Temperature Coefficient of Voc	β	[%/K]	-0.27
Temperature Coefficient of P <sub>MPP</sub>	γ	[%/K]	-0.34	Nominal Module Operating Temperature	NMOT	[°F]	109±5.4 (43±3°C)

# PROPERTIES FOR SYSTEM DESIGN

	$\textbf{Maximum System Voltage V}_{\text{SYS}}$	[V]	1000 (IEC)/1000 (UL)	PV module classification	Class II
	Maximum Series Fuse Rating	[A DC]	20 Fire Rating based on ANSI/UL 61730		TYPE 2
-	Max. Design Load, Push / Pull <sup>3</sup>	[lbs/ft <sup>2</sup> ]	75 (3600 Pa)/55 (2660 Pa)		-40°F up to +185°F
	Max. Test Load, Push / Pull <sup>3</sup>	[lbs/ft <sup>2</sup> ]	113 (5400 Pa) / 84 (4000 Pa)	on Continuous Duty	(-40°C up to +85°C)

# **QUALIFICATIONS AND CERTIFICATES**

#### PACKAGING INFORMATION

UL 61730, CE-compliant Quality Controlled PV - TÜV Rheinland, IEC 61215:2016, IEC 61730:2016, U.S. Patent No. 9,893,215 (solar cells). QCPV Certification ongoing.

3 See Installation Manual





















1656 lbs 76.4 in 43.3 in 48.0 in Horizontal 24 24 32 1940mm 1100 mm 1220 mm pallets packaging 751 ka pallets modules

Note: Installation instructions must be followed. See the installation and operating manual or contact our technical service department for further information on approved installation and use of this product.

#### Hanwha Q CELLS America Inc.